AMENDMENT NO. 1 JUNE 2019
TO
IS 302-2-21 : 2018 SAFETY OF HOUSEHOLD AND SIMILAR ELECTRICAL APPLIANCES

PART 2 PARTICULAR REQUIREMENTS

Section 21 Stationary Storage Type Electric Water Heaters

(Second Revision)

(*Page* 9, *Table* 101) — Substitute the following for the existing table:

Table 101 Schedule of Type Tests
(*Clause* 101.1)

Sl No.	Tests	Ref to Clause
(1)	(2)	(3)
i)	Protection against access to live parts	**8**
ii)	Power input and current	**10**
iii)	Heating	**11**
iv)	Leakage current and electric strength at operating temperature	**13**
v)	Transient over voltages	**14**
vi)	Moisture resistance	**15**
vii)	Leakage current and electric strength	**16**
viii)	Overload protection of transformers and associated circuits	**17**
ix)	Abnormal operation	**19**
x)	Stability and mechanical hazards	**20**
xi)	Mechanical strength	**21**
xii)	Construction	**22**
xiii)	Internal wiring	**23**
xiv)	Components	**24**
xv)	Supply connection and extent flexible cords	**25**
xvi)	Terminals for external conductors	**26**

Table 1 (*Concluded*)
(*Clause* 101.1)

Sl No. (1)	Tests (2)	Ref to Clause (3)
xvii)	Provision for earthing	**27**
xviii)	Screw and connections	**28**
xix)	Clearances, creepage distance and solid insulation	**29**
xx)	Resistance to heat and fire	**30**
xxi)	Resistance to rusting	**31**

(*Page* 9, *clause* **101**) — Insert the following new clauses:

'**101.2 Acceptance Tests**

The following shall constitute the acceptance test:

Sl No.	*Test*	*Reference Clause*
i)	Protection against access to live parts	**8**
ii)	Power input andcurrent	**10**
iii)	Heating	**11**
iv)	Leakage current and electric strength at operating temperature	**13**
v)	Moisture resistance	**15**
vi)	Leakage current and electric strength	**16**
vii)	Construction	**22**
viii)	Provision for earthing	**27**

NOTE — For the purpose of the acceptance test, test humidity treatment is done for 24 h while conducting the test for moisture resistance as given in **15** of IS 302-2-21.

101.3 Routine Test

The schedule of routine test shall be as given in Annex A of IS 302 (Part 1).'

(*Page* 9, *Annex* A) — Delete.

(ETD 32)

Publication Unit, BIS, New Delhi, India